



GOVERNMENT OF KERALA

Abstract

AMRUT - Revision of Administrative Sanction of the work Multi Level Car Parking System in Corporation Premises & Putharikanadam Maithanam - Sanctioned - Orders Issued

LOCAL SELF GOVERNMENT (DC) DEPARTMENT

G.O.(Rt)No.1897/2021/LSGD Dated,Thiruvananthapuram, 04/10/2021

Read 1 G.O (Rt) No. 5/2018/ LSGD dated 01/01/2018

2 Minutes of 28th State High Powered Steering Committee of AMRUT dated 06/08/2021

3 Letter No. UP1/1374/2019/AMRUT/General/10 dated 25/08/2021 from Mission Director, AMRUT

ORDER

As per the letter read as 3rd paper above the Mission Director, AMRUT informed that the the proposal for the revision of AS of the work- Multi Level Car Parking System in Thiruvananthapuram Corporation Premises & Putharikanadam Maithanam under Urban Transport Sector, being implemented by the Thiruvananthapuram Corporation, was placed before the 28th SHPSC.

Reasons for Revision of AS

MLCP @ Corporation Premises:

- i. Number of MLCP main structure footing increased to 24nos. from 12nos.
- ii. As per the new fire norms sump room size was increased from 13.1m x 6.4m to 23m x 6m.

- iii. Addition of items such as Grade Beam in foundation and MLCP roofing, which were not considered in the original estimate prepared by KITCO.
- iv. Depth of foundation increased to 3.5m from 2m as recommended in the soil test result.
- v. Addition of items i.e. general lighting and liaising charges which were not included in the original estimate prepared by KITCO.

MLCP @ Putharikandam Maithanam:

- i. In the confirmatory soil test pile footing was recommended for MLCP. In the original estimate isolated footing was considered.
- ii. Addition of items such as MLCP roofing, cladding, lightning conductor, MLCP lighting and fire stair, which were not considered in the original estimate prepared by KITCO.
- iii. Items such as two-wheeler parking, solar panels and toilet block to be removed from project scope to limit the estimate. These items to be taken up simultaneously under Corporation's own fund.

2. As per the order read as 1st paper above, Administrative Sanction for the project was accorded for Rs. Rs.17.64 Cr. (MLCP @ Corporation Premises: Rs.5.64 Cr. & MLCP @ Putharikandam: Rs.12 Cr.) Total Additional Amount Required is Rs.1.2688 Cr., and the Mission Director, AMRUT informed that the same can be met from the AS- TS savings of work- MLCP @ Medical College Trivandrum.

3. The 21st SLTC meeting held on 27.07.2021 decided to recommend the revision of AS from Rs.17.64 Cr. to Rs.18.91 Cr, due to tender excess and due to additional works of the two sub-works, to the SHPSC subject to approval of Municipal Council for meeting 50% of cost due to tender excess.

4. The 28th SHPSC discussed the matter in detail and took the following decisions.

(1) The Committee took note of the reduction of scope of scope of works such as two-wheeler parking, solar panels and toilet block from the work- MLCP @ Putharikandam Maithanam.

(2) The Committee accorded sanction to revise the AS of the work from Rs.17.64 Cr. to Rs.18.91 Cr. subject to the conditions that the 50% of cost due to tender excess shall be met by the ULB & balance 50% shall be met by the State and that the fund requirement shall be met from the savings in the work “MLCP @ Medical College Trivandrum”.

(3) The work to be completed by 31.03.2022.

(4) Project Manager - Smt. Rani G., Executive Engineer, Thiruvananthapuram Corporation.

5. Government have examined the matter in detail and pleased to accord sanction to revise the Administrative Sanction of the work Multi Level Car Parking System in Corporation Premises & Putharikanadam Maithanam under Urban Transport Sector, being implemented by the Thiruvananthapuram Corporation, from Rs.17.64 Cr. to Rs.18.91 Cr. subject to the conditions that the 50% of cost due to tender excess shall be met by the ULB and balance 50% shall be met by the State and that the fund requirement shall be met from the savings in the work “MLCP @ Medical College Trivandrum” and the work to be completed by 31/03/2022 by Project Manager Smt. Rani G, Executive Engineer, Thiruvananthapuram Corporation.

(By order of the Governor)

John V Samuel Ias

Deputy Secretary

To:

Mission Director, AMRUT

The Principal Accountant General (Audit/ A&E/ LBA &A)

The Information Officer, (Web & New Media) I&PRD

Executive Director, Information Kerala Mission

Stock File/Office Copy

Forwarded /By order

Section Officer